

GWSSA HOLYOAK WATER IMPROVEMENTS 2025

Addendum 1

March 6, 2026

Planholder:

This Addendum 1 shall become part of the plans, specifications and contract documents of the above-referenced project, and all provisions of the contract shall apply hereto. Bidders shall acknowledge receipt of all addenda by number in the space provided in the bid documents.

1. Bidders submitted the following questions to the Engineer. See responses to questions below:

Q: Is there a dump site that the contractor can use?

A: No, the contractor will be responsible for finding a dump site. GWSSA may be able to help locate one.

Q: What is the EOPC?

A: \$1.3 million

Q: Would it be possible to shut down Holyoak and Murphy Lane during time of construction?

A: No, plan on keeping 1 lane open for traffic.

Q: Will there need to be imported backfill within the UDOT ROW or would native soil be acceptable?

A: Imported backfill will need to be used for anything within the UDOT ROW. Imported backfill must meet UDOT classification A-1.

Q: Will both mains need to be live for connections and services?

A: Yes, the existing lines will need to remain live until the new water main and services are tied in, and down times will need to be minimized.

Q: Are there utilities on Holyoak?

A: The water and sewer mains and services are shown based on available information, but contractors should also expect to encounter other utilities not shown in the drawings.

Q: Is the 7" UDOT asphalt included in the 498 SY in the Bid Schedule?

A: Yes it was, we will be separating the quantities into separate line items within the Bid Schedule which will be attached within this Addendum.

Q: What is the difference in bid item #'s 27 and 29? Could you provide clarification on where one is used over the other and why?

A: Per Sheet Note 3 on the P sheets, any services affected by the project that don't currently have a dual check valve will have the yoke replaced. We anticipate using the "1" Service Meter Setter Assembly" item (13 and 29) where we're relocating a meter pit, and the "Install Dual Check Water Service Meter Yoke" (15 and 31) where we're not relocating the meter pit but need to replace the yoke due to its missing the dual check.

Q: The plans indicate that we are not to splice the service connection lines (Note 2). Are the meters on Murphy Lane that are behind homes and in private property going to be relocated to the property lines?

A: Yes, wherever it will be feasible we will relocate the meter pits to the property lines and will have a splice on the customer-owned side of the meter to minimize disturbance.

2. The Bid Schedule has been updated to split line item 15 into two separate line items to distinguish the 3" Bituminous Surfacing and the 7" Bituminous Surfacing.
3. The Bid Schedule has been updated to include a line item for imported backfill for the trench along Highway 191.

Sincerely,



Devan Shields, P.E.
Project Engineer
Sunrise Engineering

Attachments:

Bid Schedule

BID SCHEDULE

CONTRACT FOR:

HOLYOAK WATER IMPROVEMENTS 2025

The undersigned Bidder, having examined and determined the scope of the Contract Documents, hereby proposes to perform the work described herein for the following unit prices or lump sum amounts.

Note: <i>Bids shall include sales tax and all other applicable taxes and fees</i> <i>All bids shall be checked for errors. If errors are made, unit prices shall govern and corrections will be made according to the unit price and totals will be revised to reflect the corrections.</i>						
No.	Meas. & Pmt.	Item	Quantity	Unit	Unit Price	Amount
1	02000	Mobilization	1	Lump Sum		
2	02005	Traffic Control	1	Lump Sum		
3	02020	Subsurface Investigation	10	Hour		
4	02105	Imported Trench or Structural Backfill (Hwy 191)	1,510	Lineal Feet		
5	02105	Imported Pipe Bedding	4,820	Lineal Feet		
6	02105	Untreated Base Course	470	Cubic Yard		
7	02222	8" PVC Pipe DR18 AWWA C-900	4,820	Lineal Feet		
8	15230	8" Gate Valve	19	Each		
9	15230	Reconnect Existing Fire Hydrant	5	Each		
10	15230	New Fire Hydrant Assembly	3	Each		
11	15230	Remove Exist. Hydrant	3	Each		
12	15234	Existing Service Reconnection (3/4" or 1")	15	Each		
13	15234	1" Service Meter Setter Assembly	19	Each		
14	15234	1" IPS SDR 9 Polyethylene Service Lateral	268	Lineal Feet		
15	15234	Install Dual Check Water Service Meter Yoke	15	Each		
16	02511	Replace 3" Bituminous Surfacing	406	Sq. Yard		
17	02501SP	Replace 7" Bituminous Surfacing	92	Sq. Yard		
18	02520	Pavement Cutting	3,370	Lineal Feet		
19	15232	Combination Air Valve Assembly	1	Each		
20	02015	Clear and Grub	1	Lump Sum		
BID ALTERNATE 1 - MURPHY LANE						
21	02105	Imported Trench or Structural Backfill	1,380	Lineal Feet		
22	02105	Imported Pipe Bedding	1,380	Lineal Feet		
23	02105	Untreated Base Course	130	Cubic Yard		
24	02222	8" PVC Pipe DR18 AWWA C-900	1,380	Lineal Feet		
25	15230	8" Gate Valve	2	Each		
26	15230	Reconnect Existing Fire Hydrant	1	Each		
27	15231	New Fire Hydrant Assembly	1	Each		
28	15234	Existing Service Reconnection (3/4" or 1")	3	Each		
29	15234	1" Service Meter Setter Assembly	4	Each		
30	15234	1" IPS SDR 9 Polyethylene Service Lateral	180	Lineal Feet		
31	15234	Install Dual Check Water Service Meter Yoke	3	Each		
TOTAL						

The undersigned Bidder certifies that this proposal is made in good faith, without collusion or connection with any other person or persons bidding on the work.

Seal (if bid is by Corporation)

Respectfully Submitted:

Bidder: _____

Signature _____

Title: _____

License No. _____

Address: _____

Date: _____
