

EXHIBIT "A"
EAGLE COUNTY 2026 OVERLAY PROJECT

PROJECT #1

Location	Description	QTY	Unit	Unit price	Amount
Bellyache Ridge Bellyache Ridge Rd. Big Dipper and Little Dipper (C.R. 35, C.R. BY35A and C.R. BY35B)	Overlay Bellyache Ridge Rd From 3.1 MM approximately 12,060 LF to end of pavement with 2.5" of HBP -SX, PG 58-28 (see #1 and #2 Exhibit "B" for a list of details)	4400	Ton		
	Overlay all of Big Dipper and Little Dipper Rd. with 2.5" of HBP-SX, PG 58-28. (see #1 for Exhibit B for a list of details)	1640	Ton		
	Full width mill (see Exhibit "B" #1 for list details)	43,392	Sq. Yd.		
	Emulsified asphalt (tack) CSS-1H or SS-1H	8,678	Gal.		
	Materials sampling, testing, and inspection. (see #7 Exhibit "B")	1	Lump sum		
	Construction zone traffic control	1	Lump sum		
	Manhole and Water valve adjustments	1	Lump Sum		
TOTAL FOR PROJECT #1					

Contractor name: _____
Contract Time: October 30, 2026
Contractor Entity name: _____
Title of Person Signing on behalf of Contractor: _____
Contractor Signature: _____
Printed Name of Person Signing on behalf of Contractor: _____
Attestation as required: _____
Address and telephone number and state of incorporation or formation: _____

PROJECT #2

Location	Description	QTY	Unit	Unit price	Amount
Lake Creek Eagle Crest Rd. (CR. LC5), Idlewild Place (CR. LC7), Elk Place (CR. LC6), Polar Star (CR. LC1) and Jackman Ranch Rd. (CR. LC2)	Overlay all pavement on Eagle Crest Rd., Idlewild Pl., Elk Pl., Polar Star and Jackman Ranch Rd. with 2.5" of HBP -SX, PG 58-28 (see #1 and #2 Exhibit "B" for a list of details)	2,275	Ton		
	Full width mill (see #1 Exhibit "B")	16,340	Sq. Yd.		
	Emulsified asphalt (tack) CSS-1H or SS-1H	3,268	Gal.		
	Materials sampling, testing, and inspection. (see #7 Exhibit "B")	1	Lump sum		
	Construction zone traffic control	1	Lump sum		
TOTAL FOR PROJECT #2					

Contractor name: _____

The Total Amount Bid for Project # 2 is _____

(Please write out bid amount)

Contract Time: October 30, 2026

Contractor Entity name: _____

Title of Person Signing on behalf of Contractor: _____

Contractor Signature: _____

Printed Name of Person Signing on behalf of Contractor: _____

Attestation as required: _____

Address and telephone number and state of incorporation or formation: _____

PROJECT #3

Location	Description	QTY	Unit	Unit Price	Amount
Basingdale Blvd. (C.R. V12)	Overlay Basingdale Blvd. from County line approximately 635 lf to end of pavement with 2.5" of HBP -SX, PG 58-28 (see #1 and #2 Exhibit "B" for a list of details)	240	Ton		
	Full width mill (see #1 Exhibit "B")	4,651	Sq. Yd.		
	Emulsified asphalt (tack) CSS-1H or SS-1H	930	Gal.		
	Materials sampling, testing, and inspection. (see #7 Exhibit "B")	1	Lump sum		
	Manhole and Water valve adjustments	1	Lump Sum		
	Construction zone traffic control	1	Lump sum		
TOTAL FOR PROJECT #3					

Contractor name: _____

The Total Amount Bid for Project # 3 is _____

(Please write out bid amount)

Contract Time: October 30, 2026

Contractor Entity name: _____

Title of Person Signing on behalf of Contractor: _____

Contractor Signature: _____

Printed Name of Person Signing on behalf of Contractor: _____

Attestation as required: _____

Address and telephone number and state of incorporation or formation: _____