

EXHIBIT "B"
2026 OVERLAY PROJECT - SPECIAL PROVISIONS

- #1. Full width mill road surface to a depth of 2". Asphalt shall be applied with a 1" leveling and a 1.5" top lift for a total of 2.5" overlay for Project 1, 2, and 3.
- #2. **Proj. 1** will start approximately at the 3.1 mm from Cattle Guard at bottom
Proj. 2 will Start at West Lake Cr. Rd. intersections with Eagle Crest and Polar Star
Proj. 3 will Start at the Town of Vail / Eagle County Line
- #3. Hand patch with HMA (hot mix asphalt) any irregularities left from milling process.
- #4. The hot mix asphalt shall be no less than 260 degrees F behind the paver as it is applied.
- #5. **Proj.1, 2, and 3** Milled asphalt can be hauled to the Eagle County Landfill
- #6. Contractor shall be responsible for manhole and valve box counts.
- #7. Materials testing and sampling shall be performed at 500 ton intervals or a minimum of one per day.
- #8. Contractor shall be responsible for notification of project dates to affected residents and motorists including detours and delays. Contractor shall notify Road and Bridge Director of any necessary detours and provide an MHT.
- #9. Each project will be looked at individually to determine bid awards.
- #10. Contractor shall be responsible for measuring and calculating all quantities for bid.
- #11. Material quantities may be adjusted depending on bid results.