

EXHIBIT "B"

2026 CHIPSEAL PROJECT - SPECIAL PROVISIONS

- #1.** Chipseal will be applied on 5280 LF of new AMA paved surface on Project #1. Project #2 will be approximately 6400 LF on older asphalt. Application rate potential of 0.4 to 0.5 gallons per Yd² on the fresh asphalt.
- #2.** Time for start and completion of work will be from May, 2026 to September 30, 2026
- #3.** Chips can be stockpiled on or near the project site on Project #1. For Project #2 chips can be stockpiled at the intersection of Lake Rd. and Meile Ln.
- #4.** Contractor shall be responsible for measuring and calculating all quantities for bid.