



MHTN
ARCHITECTS

Addendum No. 03

Issued: 4 March 2026

Project Name: **SJSD Monticello High School**

Project No.: 2023554.01

Addendum No. 03 to the Construction Contract for the above-referenced project:

All Contractors submitting proposals on the above-captioned project shall be governed by the following changes and explanations to the Bid Documents, dated February 10, 2026, and shall submit their bids in accordance therewith:

A. Changes to the Project Manual

Changes to attached Specification Sections are indicated in red text with deleted text, if applicable, removed from the Section. Where articles, paragraphs, or subparagraphs are inserted or deleted, renumber successive articles, paragraphs, or subparagraphs accordingly.

X3.1 Section 097260 - Tackable Wallcovering:

1. Insert Subparagraph 1.2 A 2 as indicated re: Resilient cork/linoleum tackable wallcovering.
2. Revise Paragraph 2.1 A as indicated re: Drawing Designation **TCK1**.
3. Add Paragraph 2.1 B as indicated re: Resilient, Tackable, Linoleum Surface System – **TCK2**.
4. Revise Subparagraph 2.2 B 1 b as indicated re: Size.
5. Insert Paragraph 3.2 B as indicated re: Gypsum Board Surface:
6. Insert Paragraph 3.2 C as indicated re: Painted Surface.

B. Changes to the Drawings

Architectural

A3.1 Sheet A410 – Interior Elevations

1. Added TCK2 identifier to tackable wall surface to match updated specifications.

A3.2 Sheet A640– Finish Schedule

1. Add description of Vinyl wall covering over tackable wall system Basis of Design Onnit TWS & Koroseal wall covering adhered to TWS.

End of Addendum 03

SECTION 097260 - TACKABLE WALLCOVERING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specifications Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Polyester felt wallcovering.
 - 2. Resilient fiberboard/vinyl tackable wallcovering.
 - 3. Accessories.
- B. Related Requirements:
 - 1. Section 064023 "Interior Architectural Woodwork" for wood sheathing substrate and plastic laminate finished frames used in conjunction with tackable wallcovering.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include data on physical characteristics, durability, fade resistance, and fire-test-response characteristics.
- B. Shop Drawings: Show location and extent of each wall-covering type. Indicate pattern placement seams and termination points.
- C. Samples for Initial Selection: For each type of wall covering.
- D. Samples for Verification: For each type of wall covering and for each color, pattern and texture specified, 7 by 9 inches in size.
- E. Product Schedule: For wall coverings. Use same designations indicated on Drawings.
- F. Installation Instructions.

1.4 INFORMATIONAL SUBMITTALS

- A. Product Test Reports: For each wall covering, for tests performed by a qualified testing agency.

1.5 CLOSEOUT SUBMITTALS

- A. Maintenance Instructions: Include precautions against cleaning materials and methods that may be detrimental to finishes and performance.

1.6 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials, from the same production run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Wall-Covering Materials: For each type, color, and texture, full width by length equal to 10 percent of amount installed.

1.7 QUALITY ASSURANCE

- A. Surface Burning Characteristics Classification: Provide materials that meet classification ratings below:
 - 1. ASTM E84 (Flame Spread and Smoke Developed): I/A.
- B. Single Source Responsibility: Obtain tackable wallcovering system components from a single source.
- C. Deliver materials in original factory packaging, labeled with manufacturer, brand name, size, color, and lot number.
- D. Store materials in original, undamaged packaging inside a well-ventilated area protected from weather, moisture, soiling, and extreme temperatures.
- E. Maintain room temperature within the storage area at not less than 68 degrees Fahrenheit during the period materials are stored.
- F. Mock-ups: Prepare mock-ups for architect's review and to establish requirements for seaming and finish trim.
 - 1. Correct areas, modify method of application/installation, or adjust finish texture as directed by architect to comply with specified requirements.
 - 2. Maintain mock-ups accessible to serve as a standard of quality.
 - 3. Install sample panel of each type of wallcovering specified.
 - 4. Install panels in areas designated by Architect.

1.8 FIELD CONDITIONS

- A. Maintain ambient temperature within the building at not less than 68 degrees Fahrenheit for a minimum of seventy-two hours prior to beginning of installation.
- B. Do not install tackable wallcovering until the space is enclosed and weatherproof.
- C. Do not install tackable wallcovering until temperature is stabilized and permanent lighting is in place.

1.9 WARRANTY

- A. Submit manufacturer's limited five-year written warranty against manufacturing defects.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. **Sound-Absorbing Wall Panel System – TCK1:** Manufacturer's standard panel construction consisting of 100 percent PET (polyester) felt.
1. Basis-of-Design Product: Subject to compliance with requirements, provide Acoufelt; Solid 12mm wall panels or comparable product by one of the following:
 - a. J2 Systems.
 - b. Turf Design
 2. Panel Shape: Shapes as indicated on Drawings, or, if not indicated, as selected by Architect from manufacturer's standard shapes.
 3. Mounting: Back mounted with manufacturer's standard adhesive, secured to substrate.
 4. Reveals between Panels: As selected by Architect from Manufacturer's full range.
 5. Edge Profile: Square.
 6. Acoustical Performance: Sound absorption NRC of not less than 0.45.
 7. Nominal Thickness: 12 mm .
 8. Panel Sizes: As indicated on Drawings, or, if not indicated, as selected by Architect from standard sizes.
- B. **Resilient, Tackable, Linoleum Surface System – TCK2:** High-performance vinyl surface wrapped over fiberboard core.
1. Basis-of-Design Product: Subject to compliance with requirements, provide ONNiT Systems; Vinyl-Covered Tackable Wall Panels
 2. Panel Width: 48 inches.
 3. Panel Height: Up to 10 feet.
 4. Nominal Thickness: 1/2 inch.
 5. Panel Shape: Shapes as indicated on Drawings, or, if not indicated, as selected by Architect from manufacturer's standard shapes.
 6. Mounting: Back mounted with manufacturer's standard adhesive and mechanically fastened trim, secured to substrate.
 7. Reveals Between Panels: Manufacturer's standard aluminum trim color matched to panel.
 8. Edge Profile: Square.
 9. Acoustical Performance: Sound absorption NRC of not less than 0.45.
 10. Panel Sizes: As indicated on Drawings, or, if not indicated, as selected by Architect from standard sizes.
 11. Vinyl Wallcovering: Koroseal; Desert Sand 5521-90.
 - a. Color: As selected by Architect from manufacturer's full range.
 - b. Total Weight: 20.0 ounce ply.
 - c. Backing: Woven
 - d. ASTM F793: Category V, Type II.

2.2 ACCESSORIES

- A. Adhesive: Solvent-free, SBR type linoleum adhesive (L-910) or polyvinyl acetate dispersion type (contact adhesive) when used in a press.
- B. Trim for Tackable Wall:
 - 1. Manufacturer's standard "J" trim at panel perimeter and "H" trim at vertical edges of adjoining panels.
 - a. Finish: Manufacturer's standard baked enamel or powder coated painted finish matching panel faces.
 - a. Size: Manufacturer's standard exposed face dimension.
- C. Push-Pins: 24 push pins per room, translucent.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas and conditions in which tackable wallcoverings will be installed.
- B. Complete finishing operations, including painting, before beginning installation of tackable wallcovering materials.
- C. Notify the Contractor and Architect in writing of any conditions detrimental to the proper and timely completion of the installation.
- D. Beginning of installation means acceptance of surface conditions.

3.2 PREPARATION

- A. Surface Preparation: Remove hardware, accessories, plates, and similar items to allow tackable wallcovering to be installed.
- B. Gypsum Board Surface: Recess nails and screws. Repair irregular tape joints, sand and remove dust.
- C. Painted Surface: Remove loose paint or scale. Sand surface of enamel or gloss paint and wipe clean with damp cloth.
- D. Ensure casework surfaces indicated to receive tackable wallcovering are suitable for use under tackable wallcoverings.

3.3 APPLICATION

- A. Comply with manufacturer's printed installation instructions.

- B. Cut sheets to size including a few inches of overage. Allow sheets to lay flat for at least twenty-four hours prior to the application. Mark roll direction and sequence on the backside of each sheet. Hang sheets in sequence as cut from the roll, do not reverse sheets.
- C. Permanent HVAC system should be set to 68 degrees Fahrenheit for at least seventy-two hours prior to, during, and after the installation.
- D. Back roll each sheet prior to the installation to release curl memory.
- E. For seamed applications, using a seam and strip cutter remove the factory edge of one sheet. Using the same tool, overlap and trace cut the mating edge of the second sheet. Repeat this step for as many sheets as required for the job.
- F. Scribe, cut, and fit material to butt tightly to adjacent surfaces, built-in casework, and permanent fixtures and pipes.
- G. Apply adhesive with a 1/16 inch square notch trowel to the area to receiving the sheet (apply enough for one sheet at a time).
- H. Work from top to bottom then side to side. Roll sheet firmly into adhesive for positive contact and to remove air bubbles.
- I. Remove adhesive residue immediately after each panel is hung with a mild soap/water solution and a soft cloth/sponge.

3.4 CLEANING

- A. Clean wallcovering using a sponge with a neutral pH cleaning solution. Do not use abrasive cleaners. Rinse thoroughly with water and let dry before using.
- B. Remove adhesive while wet.

3.5 PROTECTION

- A. Protect installed product and finish surfaces from damage during construction.

END OF SECTION 097260

Autodesk Docs: 2023554 - SUSD School Projects (Bidding) ES - MHS - ARL MS - MCES - SJH/2024-2023554 SUSD MHS Secure Vestibule INT
3/4/2026 1:37:34 PM



INTERIOR ELEVATIONS GENERAL NOTES

RE: North American Architectural Woodwork Standards v3.0 (NAAWS), Cabinet Design Series for cabinet types.

1. RE: G300 for Interior Wall Types.

RE: A640 for the Finish Schedule.

Dimensions shown to walls or casework are to finished face of wall or cabinet, UNO.

Equipment indicated by dashed lines is a general representation and shown for coordination purposes only.

Mechanical, electrical, plumbing and telecom rough-in locations are shown for general coordination purposes only. Refer to mechanical, electrical, plumbing and telecom drawings.

Countertops: 25" deep with 4" high backsplash, UNO. Provide sidesplashes at walls, tall cabinets or similar transitions.

Blocking: Provide blocking in walls at cabinets, wall-mounted accessories, equipment, display boards and similar items.

Finishes: Finishes are required on all exposed and semi-exposed surfaces, UNO. Wall elevations are not shown for walls where the Finish Schedule is deemed adequate to convey the intent.

Cabinet Locks: Provide locks on cabinet drawers and doors, keyed alike by room, UNO.

Casework Finishes: Provide laminate finishes on all exposed and semi-exposed surfaces as required by the specifications. Provide laminate finishes on concealed surfaces if required by the specifications. Refer to NAAWS Section 10.4.4 for definitions of exposed, semi-exposed and concealed surfaces.

LEGEND - INTERIOR ELEVATION

	PAINTED GYPSUM BOARD		TACK BOARD
	GLAZING/SCHEDULED WINDOW SYSTEM		TV MONITOR; SEE ELECTRICAL
	TACKABLE WALL SURFACE TCK2		WHITE BOARD

KEYNOTES - INTERIOR

- ST. STL. COUNTER TOP W/ HEAVY DUTY WALL SUPPORTS
- FELT TACK
- T1A
- U-SHAPED ST. STL. WALL CAP W/ 4" LEG
- OVERHEAD DOOR HOUSING EXTENDS ABOVE CEILING
- SS1 WINDOW SILL - BEYOND
- P-LAM & SS1 FINISHES EXTENDS TO WINDOW SIDE OF CABINETS
- WINDOW BEYOND RE: FLOOR PLAN

SAN JUAN SCHOOL DISTRICT
MONTICELLO HIGH SCHOOL - SECURITY UPGRADES
148 SOUTH 200 WEST
MONTICELLO, UTAH 84535

2023 MHTN ARCHITECTS, INC.
Confidentiality Notice
This document is intended for use on the Project identified herein by individuals and companies involved in the design, permitting, bidding and construction of the Project. MHTN ARCHITECTS, INC. grants written rights to distribute and reproduce this document for the express purpose only. Distribution, printing or copying this document for purposes other than those indicated is strictly prohibited. If a digital copy of this document is received in error, please delete it.

SEAL

STATE OF UTAH
CLIFFORD HOWARD CURTIS
No. T2019-0001
06 FEBRUARY 2022
LICENSED ARCHITECT

MHTN PROJECT NO. 2023554.01

Original drawing is 30 x 42. Do not scale contents of this drawing.

REVISIONS
CONTRACTOR TO VERIFY DRAWINGS IN FIELD USE REFLECT LAST REVISION DATE.

NO.	DATE	DESCRIPTION
1	02/26/2026	Addendum #1
3	03/04/2026	Addendum #3

ISSUE
CONSTRUCTION DOCUMENTS
06 FEBRUARY 2026

SHEET NAME
INTERIOR ELEVATIONS

SHEET NUMBER

A410

Autodesk Docs:2023554 - SUSD School Projects (Bidding ES - MHS - APR, MS - MCES - S.U./V./24 - 2023554 SUSD MHS Secure Vestibule v1 3/4/2026 1:37:34 PM)

FINISH SCHEDULE												
RM #	ROOM NAME	FLOOR FINISH	BASE FINISH	WALL				CEILING FINISH	CABINET FINISH	COUNTER TOP FINISH	REMARKS	RM #
				NORTH WALL FINISH	EAST WALL FINISH	SOUTH WALL FINISH	WEST WALL FINISH					
A100	VESTIBULE	CPT2		WT7	WT7	WT7	WT7		----	----		A100
A101	LOBBY	RES1, RES2, RES3, RF1	TB2	PT1/ WT1-WT5, WT8	WT8	----	----		----	----	SEE A661 FOR TILE PATTERNS AND TILE BENCH INFO	A101
A102	RECEPTION	CPT1	RB1	PT1	PT1	PT1	PT1	ACP1/ GB1	PLAM1/ PLAM2/ PLAM3	SS1	SS1 WINDOW SILL 	A102
A103	OFFICE	CPT1	RB1	PT1	PT1	PT1	PT1	ACP1	ACP1	----		A103
A104	PRINCIPAL	CPT1	RB1	PT1	PT1	PT1	PT1	ACP1	----	----		A104
A105	OFFICE	CPT1	RB1	PT1	PT1	PT1	PT1	ACP1	----	----		A105
A106	OFFICE	CPT1	RB1	PT1	PT1	PT1	PT1	ACP1	----	----		A106
A107	SHOWER	FT1	TR4	WT1	WT1	WT1	WT1	GB2	----	----		A107
A108	OFFICE	CPT1	RB1	PT1	PT1	PT1	PT1	ACP1	----	----		A108
A109	CONFERENCE	CPT1	RB1	PT1	PT1	PT1	PT1	ACP1	PLAM3	SS1		A109
A110	HALL	CPT1	RB1	PT1	PT1	PT1	PT1	ACP1	----	----		A110
A111	HALL	CPT1	RB1	PT1	PT1	PT1	PT1	ACP1	----	----		A111
A112	OFFICE	CPT1	RB1	PT1	PT1	PT1	PT1	ACP1	----	----		A112
A113	OFFICE	CPT1	RB1	PT1	PT1	PT1	PT1	ACP1	----	----		A113
A114	FACULTY LOUNGE	ER	ME	ER	ER	ME	ER	ER	----	----		A114
A115	WORK ROOM	ME	ME	ME	ME	ME	ME	ME	ME	ME		A115
A116	MEDIA CENTER	CPT1	ME	ER	ER	ER	ER	ER	ER	ER		A116
A117	CONCESSIONS	RES2	RB1	PT1	PT1	PT1	PT1	ACP2	ACP2	SSTL		A117
A118	HOME ECONOMICS	RES2	RB1	PT1	PT1	PT1	PT1	ER	ER	ER	SS1 WINDOW SILL	A118
A119	STORAGE	RES1	RB1	PT1	PT1	PT1	PT1	ACP2	----	----		A119
A120	GYM STORAGE	RES1	RB1	PT1	PT1	PT1	PT1	ACP2	----	----		A120
A121	MEN	FT2	TR4	WT9, WT10, WT11, WT12	WT9, WT10, WT11, WT12	WT9, WT10, WT11, WT12	WT9, WT10, WT11, WT12	GB2	----	SS1	SS1 WINDOW SILL, LAMINATED PRIVACY FILM	A121
A122	WOMEN	FT2	TR4	WT9, WT10, WT11, WT13	WT9, WT10, WT11, WT13	WT9, WT10, WT11, WT13	WT9, WT10, WT11, WT13	GB2	----	SS1	SS1 WINDOW SILL, LAMINATED PRIVACY FILM	A122
A123	CUST.	SC	RB1	PT1	PT1/ WT9	PT1/ WT9	PT1	----	----	----		A123
A131	CORRIDOR	ER	ER	ER	ER	ER	ER	ER	----	----		A131
A132	CUSTODIAL	ER	ER	ER	ER	ER	ER	ER	----	----		A132
A133	MECHANICAL	ER	ER	ER	ER	ER	ER	ER	----	----		A133

FINISH SCHEDULE LEGEND

GENERAL

EX - EXISTING TO REMAIN - PATCH WHERE DISTURBED BY CONSTRUCTION

ME - MATCH EXISTING

FLOOR FINISHES

CPT1 - CARPET TILE
MANUFACTURER: SHAW CONTRACT
PRODUCT: SIDE BY SIDE TILE, 5T452
COLOR NAME/ NUMBER: JOIN COLOR (50865)
INSTALL METHOD: STAGGER

CPT2 - WALK-OFF CARPET TILE
MANUFACTURER: MILLIKEN
PRODUCT: OBEX, CUT X, STIPPLE
COLOR NAME/ NUMBER: STX174 - 133 TAUPE
INSTALL METHOD: MONOLITHIC

RES1 - RESILIENT TILE
MANUFACTURER: MILLIKEN
PRODUCT: GOUACHE
COLOR NAME/ NUMBER: GOU153 NEUTRAL TINT

RES2 - RESILIENT TILE
MANUFACTURER: MILLIKEN
PRODUCT: GOUACHE
COLOR NAME/ NUMBER: GOU144 PARCHMENT

RES3 - RESILIENT TILE
MANUFACTURER: MILLIKEN
PRODUCT: GOUACHE
COLOR NAME/ NUMBER: GOU146 RUST ORANGE

RF1 - RUBBER - STAIR TREAD
MANUFACTURER: ROPPE
DESIGN: #30 DIAMOND SQUARE TREAD
COLOR: CHARCOAL

FT1 - PORCELAIN TILE MOSAIC
MANUFACTURER: DALTILE
PRODUCT: HAUT MONDE
COLOR: GLITTERATI GRANITE, HM03
SIZE: 2" X 2" MOSAIC
GROUT:

FT2 - PORCELAIN TILE
MANUFACTURER: DALTILE
PRODUCT: HAUT MONDE
COLOR: GLITTERATI GRANITE, HM03
SIZE: 24" X 24"
GROUT:

BASES

RB1 - RUBBER BASE
MANUFACTURER: ROPPE
TYPE: 4" COVED
COLOR: CHARCOAL

WALL FINISHES

ME - PAINT TO MATCH EXISTING

PT1 - PAINT
MANUFACTURER: SHERWIN WILLIAMS
COLOR: SW7013 IVORY LACE

WT1 - WALL TILE
MANUFACTURER: CROSSVILLE
PRODUCT: COLOR BLOX 2.0
COLOR: CBX31 - COTTON SHEETS
SIZE: 4" X 12"
GROUT:

WT2 - WALL TILE
MANUFACTURER: CROSSVILLE
PRODUCT: COLOR BLOX 2.0
COLOR: CBX03 - SLINKY
SIZE: 4" X 12"
GROUT:

WT3 - WALL TILE
MANUFACTURER: CROSSVILLE
PRODUCT: COLOR BLOX 2.0
COLOR: CBX17 - I SEE THE MOON
SIZE: 4" X 12"
GROUT:

WT4 - WALL TILE
MANUFACTURER: CROSSVILLE
PRODUCT: COLOR BLOX 2.0
COLOR: CBX32 - BOOT BLACK
SIZE: 4" X 12"
GROUT:

WT5 - WALL TILE
MANUFACTURER: CROSSVILLE
PRODUCT: COLOR BLOX 2.0
COLOR: CBX37 - CAYENNE
SIZE: 4" X 12"
GROUT:

WT6 - WALL TILE
MANUFACTURER: CROSSVILLE
PRODUCT: COLOR BLOX 2.0
COLOR: CBX17 - I SEE THE MOON
SIZE: 12" X 24"
GROUT:

WT7 - WALL TILE
MANUFACTURER: CROSSVILLE
PRODUCT: COLOR BLOX 2.0
COLOR: CBX03 - SLINKY
SIZE: 12" X 24"
GROUT:

WT8 - WALL TILE
MANUFACTURER: CROSSVILLE
PRODUCT: COLOR BLOX 2.0
COLOR: CBX31 - COTTON SHEETS
SIZE: 12" X 24"
GROUT:

WALL FINISHES CONTINUED

WT9 - WALL TILE
MANUFACTURER: DALTILE
PRODUCT: COLOR WHEEL LINEAR
COLOR: MATTE ARCTIC WHITE 0790
SIZE: 8" X 24"
GROUT:

WT10 - WALL TILE
MANUFACTURER: DALTILE
PRODUCT: COLOR WHEEL LINEAR
COLOR: MATTE CHALKBOARD 0780
SIZE: 8" X 24"
GROUT:

WT11 - WALL TILE
MANUFACTURER: DALTILE
PRODUCT: COLOR WHEEL LINEAR
COLOR: MATTE SUEDE GRAY 0782
SIZE: 8" X 24"
GROUT:

WT12 - WALL TILE
MANUFACTURER: DALTILE
PRODUCT: COLOR WHEEL LINEAR
COLOR: MATTE ORANGE BURST 7097
SIZE: 8" X 24"
GROUT:

WT13 - WALL TILE
MANUFACTURER: DALTILE
PRODUCT: COLOR WHEEL LINEAR
COLOR: MATTE MUSTARD 7012
SIZE: 8" X 24"
GROUT:

WT14 - WALL TILE
MANUFACTURER: CROSSVILLE
PRODUCT: COLOR BLOX 2.0
COLOR: CBX37 - CAYENNE
SIZE: 12" X 24"
GROUT:

TCK2 - VINYL WALLCOVERING OVER TACKABLE WALL PANELS
MANUFACTURER: ONNIT - SUBSTRAIT, KOROSEAL
VINYL WALL COVERING
PRODUCT ONNIT TWS-STANDARD H SYSTEM WITH
KOROSEAL VINYL WALL COVERING
COLOR: DESERT SAND STUCCO 5521-90
TRIM: STANDARD "H" TRIM

LAMINATED PRIVACY FILM

PF1 - LAMINATED PRIVACY FILM
MANUFACTURER:
3M FINISH: MILKY MILK

CEILINGS

ACP1 - 24" X 24" ACOUSTICAL CEILING PANEL
MANUFACTURER: ARMSTRONG
PRODUCT/ STYLE: MESA
EDGE DETAIL: ANGLED TEGULAR 15/16
COLOR: WHITE

ACP2 - 24" X 48" ACOUSTICAL CEILING PANEL
MANUFACTURER: ARMSTRONG
PRODUCT/ STYLE: MESA
EDGE DETAIL: ANGLED TEGULAR 15/16
COLOR: WHITE

GB1 - PAINTED GYPSUM BOARD
MANUFACTURER: SHERWIN WILLIAMS
COLOR: SW7013 IVORY LACE

GB2 - EPOXY PAINTED GYPSUM BOARD
MANUFACTURER: SHERWIN WILLIAMS
COLOR: SW7013 IVORY LACE

OTS - OPEN TO STRUCTURE

OTSP - OPEN TO STRUCTURE, PAINTED
COLOR: SW7013 IVORY LACE

CABINET

PLAM1 - PLASTIC LAMINATE
MANUFACTURER: WILSONART
PRODUCT NAME: NEWLANDS
PRODUCT NUMBER: 8268K-17

PLAM2 - PLASTIC LAMINATE
MANUFACTURER: ARBORITE
PRODUCT NAME: CINNAMON TWILL
PRODUCT NUMBER: P-383 CA

PLAM3 - PLASTIC LAMINATE
MANUFACTURER: WILSONART
PRODUCT NAME: SESAME VELVET ELM
PRODUCT NUMBER: 15603

COUNTER TOP

SS1 - SOLID SURFACE
MANUFACTURER: WILSONART
PRODUCT NAME: NIGHT STARS
PRODUCT NUMBER: 9105CS

SSTL - STAINLESS STEEL

HM DOOR FRAME

DF1 - PAINTED FINISH, COLOR: MATCH EXISTING

DOORS

D1 - WOOD DOOR, CLEAR FINISH, TYP UNO

TRIMS AND TRANSITIONS

THR - STONE THRESHOLD
MANUFACTURER: DALTILE
FINISH: ABSOLUTE BLACK GRANITE, G771

TR1 - METAL TRANSITION (LVT TO CARPET TILE)
MANUFACTURER: POWERHOLD
PRODUCT NUMBER: LVT 131
FINISH: EA - ETCHED ALUMINUM

TR2 - METAL TRANSITION (LVT TO EXISTING VCT)
MANUFACTURER: SCHLUTER
PRODUCT NUMBER: VINPRO-T
FINISH:

TR3 - METAL TRANSITION (BENCH, DRINKING FOUNTAIN WING WALLS, OUTSIDE CORNERS)
MANUFACTURER: SCHLUTER
PRODUCT: RONDEC
FINISH: BRUSHED STAINLESS STEEL (EB)
NOTES: USE OUTSIDE CORNER AND INSIDE CORNER PIECES TO CONNECT

TR4 - METAL TRANSITION (COVED BASE)
MANUFACTURER: SCHLUTER
PRODUCT NUMBER: DILEX-HKU
FINISH: BRUSHED STAINLESS STEEL

FINISH SCHEDULE GENERAL NOTES

RE: Axxx for typical floor finish transition details

RE: A651-A652 for Floor Pattern Plans

Finishes

Provide finishes as indicated in the finish schedule. Refer to interior elevations, where drawn, for clarification, dimensions and additional information. The absence of an interior elevation does not override the requirement to provide the finish indicated in the schedule.

Where a finish is partly hidden by an object, extend that finish behind the object.

Where multiple finishes are scheduled, refer to interior elevations and floor pattern plans for transition locations.

Floor: Extend floor finishes into knee spaces at cabinets, under counters and under all other objects, which in a floor plan view may obscure the extent of the floor finish.

Base: Where base is scheduled for a room, provide base at all walls whether shown in elevation, including alcoves and offsets. At gypsum board walls, if no base is scheduled or shown in interior elevations, provide 4" rubber base.

Walls: Extend wall finishes behind cabinets, behind mirrors, and into other areas that may be hidden in elevation views.

Ceilings: Paint areas above suspended ceilings that are visible from below. Color: black.


Doors, Windows and Frames: Unless specified to be pre-finished at the factory, provide paint finish on hollow metal doors and hollow metal door and window frames. Color as indicated, or if not indicated, then as selected by the Architect. Provide specified stain finish at wood doors.

Unfinished and Primed Metal Surfaces: Paint all unfinished and primed metal surfaces that are visible with the specified system(s). Color by Architect.

Standing and Running Trim: Provide specified stain finish at wood trim.

Floor Finish Transitions at Doors: Locate floor finish material transitions that occur at doors under the center of the door, UNO.

Floor Drains: Coordinate location of floor drains with Plumbing drawings.



MHTN
ARCHITECTS


MHTN Architects, Inc.
280 South 400 West
Suite 250
Salt Lake City, Utah 84101
Telephone (801) 585-6700
www.mhtn.com

SAN JUAN SCHOOL DISTRICT
MONTICELLO HIGH SCHOOL - SECURITY
UPGRADES
148 SOUTH 200 WEST
MONTICELLO, UTAH 84535

©2023 MHTN ARCHITECTS, INC.

Confidentiality Notice
This document is intended for use on the Project identified herein by individuals and companies involved in the design, permitting, bidding and construction of the Project. MHTN Architects, Inc. grants written rights to distribute and reproduce this document for this express purpose only. Distribution, printing or copying this document for purposes other than those indicated is strictly prohibited. If a digital copy of this document is received in error, please delete it.

SEAL



MHTN PROJECT NO: 2023554.01

Original drawing is 30" x 42". Do not scale contents of this drawing.

REVISIONS:
CONTRACTOR TO VERIFY DRAWINGS IN FIELD USE REFLECT
LAST REVISION DATE.

NO.	DATE	DESCRIPTION
1	02/20/2026	Addendum #1
3	03/04/2026	Addendum #3

ISSUE

CONSTRUCTION DOCUMENTS
06 FEBRUARY 2026

SHEET NAME

FINISH SCHEDULE

SHEET NUMBER

A640