

Bid Items List Report

PIN : 22900 Project Number : F-0040(251)125 Project Name : Jurassic US-40 Fiber Optics - Segment D Concept : ITS Communication DBE Goal : 0%	Location : US-40; MP 50.86 - 175.04 & US-191; MP 353.05 - 356.06 Funding Type : Federal Region : Region 3 County : Duchesne , Uintah , Wasatch * The records highlighted in yellow indicate Principal items of work
---	--

Base Bid Items					
Container	Description				
	Line No.	Item Number	Item Name	Quantity	Unit
10 - ROADWAY	Base				
	1	015017010	Mobilization	1.00	Lump
	2	01540701*	Public Information Services	1.00	Lump
	3	015547005	Traffic Control	1.00	Lump
	4	01557700*	Portable Variable Message Signs	12.00	device day
	5	015717025	Check Dam - Fiber Roll	15,375.00	ft
	6	015717075	Drop-Inlet Barrier - Fiber Roll	32.00	ft
	7	015717115	Pipe-Inlet Barrier - Fiber Roll	29.00	Each
	8	015717140	Fiber Roll Barrier	51,828.00	ft
	9	02216700P	Test-Hole Utility (Contingency)	75.00	Each
30 - LANDSCAPING	Base				
	10	02816700*	Landscape Restoration	12,978.00	sq ft
	11	02922703P	Broadcast Seed (Plan Quantity)	2.00	Acre
60 - LIGHTING	Base				
	12	16525701P	Install State Furnished 30' Highway Luminaire Pole and Foundation	1.00	Each
70 - ITS	Base				
	13	13551700*	Building Entry	4.00	Each
	14	13553701*	Install State Furnished 1D Conduit	117,157.00	ft
	15	13553701P	Install State Furnished One 2-Inch Conduit	1,871.00	ft
	16	13553706*	Install State Furnished Three 12.7/10mm Microducts	133,408.00	ft
	17	135537065	MD4 Microduct Bundle	593.00	ft
	18	13553708*	Proof Existing Conduit	193,236.00	ft
	19	13553710*	Directional Bore	35,222.00	ft
	20	13553711*	Plow or Trench Outside of Roadway - 36in Depth	1,416.00	ft
	21	13553712*	Plow or Trench Outside of Roadway - 60in Depth	82,344.00	ft

Bid Items List Report

Base Bid Items					
Container	Description				
	Line No.	Item Number	Item Name	Quantity	Unit
70 - ITS	22	13553713*	60-Inch Depth Rock Saw Trench (Contingency)	5,280.00	ft
	23	13553714*	36-Inch Depth Rock Saw Trench (Contingency)	2,140.00	ft
	24	135547020	Polymer Concrete Junction Box Type I	2.00	Each
	25	13554703P	Install State Furnished HDPE Junction Box, Type II	2.00	Each
	26	13554704P	Install State Furnished HDPE Junction Box, Type III	158.00	Each
	27	13555702P	Install State Furnished Pole-Mounted 336 ITS Cabinet - No Paint	1.00	Each
	28	13556711P	Install State Furnished Galvanized 6-Bolt Mount CCTV Pole, 45'	1.00	Each
	29	13556712P	CCTV Pole Foundation	1.00	Each
	30	13594700*	Install State Furnished WiFi Hotspot	4.00	Each
	31	13594701P	Pull Existing Fiber Cable Through New Conduit	450.00	ft
	32	13594703*	CAT 6 Ethernet Cable	800.00	ft
	33	13594707*	Install State Furnished 144 Strand SMFO Microfiber Cable	167,099.00	ft
	34	13594708*	Install State Furnished 72 Strand SMFO Cable	373.00	ft
	35	13594709*	Install State Furnished 144 Strand SMFO Cable	165,659.00	ft
	36	13594710*	288 Strand Hub Fiber Optic Distribution Unit (FDU)	1.00	Each
	37	13594711*	72 Strand Hub Fiber-Optic Distribution Unit (FDU)	1.00	Each
	38	13594712*	120VAC Circuit	1.00	Each
	39	13594713P	Install State Furnished Fusion Splice	2,610.00	Each
	40	13594714*	6 Strand FOC Drop Cable	4,498.00	ft
	41	13594715P	Install State Furnished Fiber Optic Cable Splice Enclosure	36.00	Each
	42	13594716*	7 ft Two Post Telecommunications Rack	1.00	Each
	43	13594717*	6 Strand Pre-Terminated Drop Cable Unit	12.00	Each
	44	16530700P	#14 AWG Solid/Insulated Locate Wire	306,265.00	ft
	45	16530701P	ITS Electrical Service, MP 59.1	1.00	Lump
	46	16530702P	STATE FURNISHED POE NETWORK SWITCH	1.00	Each

Bid Items List Report

Base Bid Items					
Container	Description				
	Line No.	Item Number	Item Name	Quantity	Unit
180 - TIME AND/OR LANE RENTAL	Base				
	47	00221700*	Contract Time	Time Range: 130 - 190	Cal d