

ELECTRICAL NOTE:
XCEL ENERGY TO PROVIDE POWER AND TRANSFORMER TO TANK SITE.
CONTRACTOR TO PROVIDE SECONDARY FROM TRANSFORMER TO METER, METER TO BREAKER BOX AND CIRCUITS TO THE FOLLOWING:
1. LIGHT POST, SITE LIGHTING (EXTERIOR OUTLET ON LIGHT POLE), AND TANK VALVE CONTROLS.
CONTRACTOR TO PROVIDE ALL MATERIAL AND LABOR FOR INSTALLING ABOVE.

