

Statement of Work: Supply and Deliver Untreated Base Course (UBC)

Work Location: Arches National Park, Moab, UT

PROJECT SPECIFICATIONS

PART 1 GENERAL

1.1 DESCRIPTION & REQUIREMENTS

- A. Synopsis. Arches National Park requires supply and delivery of 800 tons of Untreated Base Course (UBC). The UBC shall not contain over approximately 2% water. The delivery amount per day is to be between 150 to 200 tons. 800 tons are to be delivered between the dates of May 20, 2026, to June 20, 2026.
- B. Location. Arches NP is approximately 5 miles north of Moab, Utah on Highway 191. Material will be off-loaded at the materials storage yard near Balanced Rock. Travel approximately 10 miles along the Park Scenic Drive to Balanced Rock and turn left (north) on a gravel road past the picnic area another 1/4 mile to the storage area (bone yard).
- C. Period of Performance. The Contractor shall be available to supply UBC for a period of May 20, 2026, to June 20, 2026.
- D. Warranty. The product shall be warranted to meet the requirements of this specification upon delivery.
- E. Submittals. The supplier shall submit a signed letter of certification stating that materials supplied will meet the requirements of Part 2 Products. This letter of certification must be included with the quote. After award the Contractor shall submit their job mix gradation as required in table two of the referenced UDOT specification 02721.

1.2 REQUIREMENTS

- A. Delivery Times and Dates. **Delivery is to be completed within the two delivery windows specified in the period of performance.** Delivery will only be allowed between 6:00 AM to 5:00 PM Monday through Thursday, no Friday, Weekend or Federal Holiday deliveries will be allowed.
- B. Period of Performance:
 - 1. The Contractor shall supply 800 tons of UBC from a period of May 20, 2026, to June 20, 2026. The delivery amount per day is to be between 150 to 200 tons.

C. Delivery:

1. The **Service Drive** located directly to the north of the Park Entrance Road will allow the delivery trucks to bypass the Entrance Station.
2. **Due to congestion on the entrance road the Contractor shall plan for delays of 15 - 30 minutes to access the Service Drive turn off between the hours of 9 am to 1 pm daily. No Contract Modifications will be approved for additional delivery time due to delays at the Park Entrance Station.**
3. The delivery amount per day is to be between 150 to 200 tons.

D. Delivery Coordination. Contact the contracting officer representative (Monday through Thursday).

E. Truck Size. It is the Contractors responsibility to assess the delivery location and determine suitable delivery trucks. However, due to the size of the delivery location and the limited amount of space to stockpile material, double belly dumps (trains) or end dump with two pups (triples) will not be allowed.

F. Delivery Quantities. Daily deliveries shall be approximately 150 to 200 tons per day to ensure that the Contractor does not overwhelm the Park's storage capacity.

G. Offloading. The Contractor shall comply with the COR on offloading procedures and locations to facilitate the Park in pushing the material up into a pile or hauling the material to the jobsite.

PART 2 PRODUCTS

2.1 PRODUCT REQUIRMENTS

- A. UBC. The UBC shall meet the requirements of UDOT Specification Section 02721 Part 2 Products (dated January 1, 2008). The aggregate class designation for Table 1 may be A, B, or C, however the Park prefers class C. UDOT Specification Section 02721 is included in the statement of work as Attachment 1.

PART 3 EXECUTION – N/A

PART 4 MEASUREMENT AND PAYMENT

- 4.1 UBC will be measured by the ton. The Contractor shall provide the COR with certified weigh tickets with each delivery. Payment will be made according to the price schedule item.

END OF SECTION