



2026 SEWER/STREETS IMPROVEMENTS PROJECT
INVITATION FOR BIDS

ADDENDUM #2

Project Number: IFB-COF-5-26
RFP Issued: March 3, 2026
Addendum #1 Issued: March 25, 2026
Addendum #2 Issued: March 26, 2026
RFP Questions Deadline: March 23, 2026
Submission Deadline: April 2, 2026, at 2:30 PM (MST)

This Addendum #2 (the "Addendum 2") is hereby issued to supplement the 2026 Sewer/Streets Improvements Project Invitation for Bids (the "IFB") with answers to questions received after the deadline. All Offerors must acknowledge receipt of this Addendum 2, and all other and future addenda to the IFB, if any, as part of their respective Bids. This Addendum does not change the deadline to submit a Bid.

Questions and Answers:

Q: Would the original lines for both the North and South parking of reed park need restriped to match current condition? If so, are the ADA Symbols for both North & South Lots to be painted or thermo?

A: Yes, the original parking lines and wheelchair-accessible symbols in the Reed Park southern parking lot will need to be reinstalled following paving. All symbols shall be thermoplastic and shall be inset slightly into the pavement and striping shall be of the same type as the rest of the street striping already outlined in the bid documents. Quantities listed in this bid schedule have been updated to reflect these changes.

Q: I was wondering where we should include the cost of removal of the existing concrete pipe on Elm ST. or if there could be a bid schedule item for the 230LF?

A: A new pay item has been added to this bid schedule to account for this work.

END OF QUESTIONS AND ANSWERS SECTION

Changes to Special Provisions

This Addendum #2 adds the following Bid Item 58 - Remove/Dispose of Exst. Sewer Pipeline



in the Special Provisions (to immediately follow Item 57 Contingency – Minor Contract Changes and come before Item 1A – 48” Precast Manhole (Polymer Concrete)):

Item 58 Remove/Dispose of Exst. Sewer Pipeline

This pay item includes furnishing all equipment, materials, and labor necessary to remove and dispose of existing sewer pipe in preparation for new sewer installation. City records indicate this pipe is 8" concrete pipe but a small portion of pipe at the downstream tie-in manhole is pvc. Payment will be made at the unit prices quoted for the actual footage of sewer pipeline removal.

END OF CHANGES TO SPECIAL PROVISIONS SECTION

Attachments:

3.26.26 Revised 2026 Sewer-Streets Improvements Bid Schedule

SUBMIT THE ATTACHED 3.26.26 REVISED 2026 SEWER-STREETS IMPROVEMENTS BID SCHEDULE WITH YOUR BID

END OF ATTACHMENTS SECTION