

**Colorado Department of Transportation
Notice To Contractors**

Printed On: **04/13/2026**

Read Order No. 003	Contract ID: C22182	Projects: NHPP5502-103
Letting Date: May 07, 2026 10:00 AM	Contract UDBE Goal: 0.00 %	
Region: 5	Guaranty: 5% of Total Bid	
Counties: OURAY	For Plans and Specs go to https://cdot.dbesystem.com	
	Work Days: 47	
	Res. 5140 Beaux Kemp	970-385-3629

Contract Description:

US 550 MP 88.6 WALL REPAIR OF DAMAGED WALL R550B088685LRA:
EXISTING DAMAGED BLOCK FACING WILL BE REMOVED TO 12" BELOW TOP OF WALL. GROUND NAILS AND A SHOTCRETE FACING WILL BE INSTALLED.

MP 90.84 L-06-P TUNNEL MAINTENANCE:
PATCH AND REPAIR EXISTING SHOTCRETE LINER IN THE TUNNEL
CLEAN OUT EXISTING 6" UNDERDRAIN BEHIND THE BARRIER.

MANDATORY PRE-BID MEETING APRIL 23, 2026 AT 10AM. SEE PROJECT SPECIAL PROVISION NOTICE TO BIDDERS FOR DETAILS.

Please register at cdot.dbesystem.com where plans and specs can be found in the "my bid solicitations" menu.

4/16/2026

One Publication: 4/16/2026

It is estimated that the total cost of all items in the bid will be:

- () Between \$0 and \$1,000,000
- (X) Between \$1,000,000 and \$5,000,000
- () Between \$5,000,000 and \$20,000,000
- () Greater than \$20,000,000

Item No.	Description	Quantity	Units
	Major Items		
202-00505	Removal of Portions of Present Structure	284.000	SF
202-04003	Clean Culvert (Special)	3.000	EACH
208-00146	Pre-fabricated Concrete Washout Structure (Type 2)	4.000	EACH
504-06406	Soil Nail	2,208.000	LF
519-01000	Epoxy Resin (Injection)	117.000	LF
601-03000	Concrete Class D	5.000	CY
620-00002	Field Office (Class 2)	1.000	EACH
626-00000	Mobilization	1.000	L S
626-01103	Public Information Services (Tier III)	1.000	L S
630-00000	Flagging	900.000	HOUR

Item No.	Description	Quantity	Units
	Major Items		
630-00012	Traffic Control Management	47.000	DAY
630-80355	Portable Message Sign Panel	2.000	EACH
630-80370	Barrier (Temporary)	250.000	LF
630-85010	Impact Attenuator (Temporary)	2.000	EACH
630-86822	Portable Traffic Signal (CWZ)	4.000	MON
632-00000	Night Work Lighting	1.000	L S
641-10000	Shotcrete	32.000	SY
641-10000	Shotcrete	267.000	SY