

Colorado Department of Transportation
Notice To Contractors

Printed On: **04/13/2026**

Read Order No. 001	Contract ID: C27298	Projects: NHPP0701-263
Letting Date: May 07, 2026 10:00 AM	Contract UDBE Goal: 0.00 %	
Region: 3	Guaranty: 5% of Total Bid	
Counties: MESA	For Plans and Specs go to https://cdot.dbesystem.com	
	Work Days: 55	
	Res. 3410 Kaitlyn Codi Clark	970-683-6351

Contract Description:

THIS PROJECT IS LOCATED ON I-70 FROM MP 31.39 TO MP 37 INCLUDING INTERCHANGE RAMPS AT EXIT 31 AND 37. THE WORK CONSISTS OF A 2 INCH HMA MILL AND FILL. THE PROJECT ALSO INCLUDES GUARDRAIL REPLACEMENT, DELINEATION, AND FINAL STRIPING.

Please register at cdot.dbesystem.com where plans and specs can be found in the "my bid solicitations" menu. 4/16/2026

One Publication: 4/16/2026

It is estimated that the total cost of all items in the bid will be:

- () Between \$0 and \$1,000,000
- () Between \$1,000,000 and \$5,000,000
- (X) Between \$5,000,000 and \$20,000,000
- () Greater than \$20,000,000

Item No.	Description	Quantity	Units
	Major Items		
202-00240	Removal of Asphalt Mat (Planing)	260,787.000	SY
202-00250	Removal of Pavement Marking	63,506.000	SF
202-01130	Removal of Guardrail Type 3	4,000.000	LF
403-34801	Hot Mix Asphalt (Grading SX) (100)	29,594.890	TON
411-03345	Asphalt Cement Performance Grade (PG 76-28)	1,776.560	TON
411-10255	Emulsified Asphalt (Slow-Setting)	15,062.000	GAL
518-03000	Sawing and Sealing Bridge Joint	491.000	LF
606-00301	Guardrail Type 3 (6-3 Post Spacing)	300.000	LF
606-00302	Guardrail Type 3 (31 Inch Midwest Guardrail System)	3,625.000	LF
606-01340	End Anchorage Type 3D	5.000	EACH
606-01370	Transition Type 3G	3.000	EACH
606-02005	End Anchorage (Flared)	7.000	EACH
612-00001	Delineator (Type I)	771.000	EACH
614-80391	Rumble Strip (Grinding)(Asphalt)	86,213.000	LF
620-00002	Field Office (Class 2)	1.000	EACH

Item No.	Description	Quantity	Units
	Major Items		
620-00012	Field Laboratory (Class 2)	1.000	EACH
625-00001	Construction Surveying (Hourly)	10.000	HOUR
626-00000	Mobilization	1.000	L S
626-01103	Public Information Services (Tier III)	1.000	L S
627-00008	Modified Epoxy Pavement Marking	746.000	GAL
627-00013	Pavement Marking Paint (High Build)	959.000	GAL
627-01010	Preformed Plastic Pavement Marking (Type I)(Inlaid)	7,042.000	SF
630-00000	Flagging	2,500.000	HOUR
630-00012	Traffic Control Management	55.000	DAY
630-80342	Construction Traffic Sign (Panel Size B)	213.000	EACH
630-80355	Portable Message Sign Panel	4.000	EACH
630-80440	Portable Rumble Strips (Temporary)	24.000	EACH
632-00000	Night Work Lighting	1.000	L S