

Bid Items List Report

PIN : 21890

Location : SR-121; MP 38.26 - 38.72 &
Steinaker Service Canal Trail
(separated from roadway)

Project Number : S-TR03(2)

Funding Type : State

Project Name : UTN: Steinaker Service Canal Trail -
Phase One

Region : Region 3

Concept : Trail - New Facility

County : Uintah

DBE Goal : %

* The records highlighted in yellow indicate Principal items of work

Base Bid Items					
Container	Description				
	Line No.	Item Number	Item Name	Quantity	Unit
10 - ROADWAY	Base				
	1	015017010	Mobilization	1.00	Lump
	2	01511700*	Construct USU Access	9,655.00	sq ft
	3	015547005	Traffic Control	1.00	Lump
	4	015717030	Silt Fence	645.00	ft
	5	015717075	Drop-Inlet Barrier - Fiber Roll	10.00	ft
	6	015717115	Pipe-Inlet Barrier - Fiber Roll	7.00	Each
	7	015717130	Stabilized Construction Entrance	1.00	Each
	8	015727020	Dust Control and Watering	500.00	1000 gal
	9	017217010	Survey	1.00	Lump
	10	018927042	Reconstruct Valve Box - Raise	1.00	Each
	11	018927052	Reconstruct Manhole - Raise	1.00	Each
	12	020567005	Borrow (Plan Quantity)	2,961.00	cu yd
	13	020567015	Granular Borrow (Plan Quantity)	22.00	cu yd
	14	022217050	Remove Tree	6.00	Each
	15	022217080	Remove Fence	5,177.00	ft
	16	02221708P	Remove Gate	4.00	Each
	17	022217095	Remove Pipe	47.00	ft
	18	022217100	Remove Pipe End Section	7.00	Each
	19	022217120	Remove Concrete Curb	425.00	ft
	20	022217165	Remove Asphalt Pavement	70.00	sq yd
	21	022317020	Clearing and Grubbing (Plan Quantity)	3.75	Acre
	22	023167020	Roadway Excavation (Plan Quantity)	1,217.00	cu yd
	23	026107384	Drainage Pipe - 15 inch, Smooth, Leak-Resistant	116.00	ft
	24	026107386	Drainage Pipe - 18 inch, Smooth, Leak-Resistant	19.00	ft
	25	026107390	Drainage Pipe - 30 inch, Smooth, Leak-Resistant	18.00	ft
	26	026137030	Circular End Section 18 inch	1.00	Each
	27	02613703P	Circular End Section 15 inch	6.00	Each

Bid Items List Report

Base Bid Items					
Container	Description				
	Line No.	Item Number	Item Name	Quantity	Unit
10 - ROADWAY	28	026137050	Circular End Section 30 inch	1.00	Each
	29	02633707P	Concrete Drainage Structure Manhole Sump - 6 Foot Diameter X 9 ft Deep	1.00	Each
	30	02633720P	Concrete Drainage Structure 3 ft Wide X 3 ft to 5 ft Deep - CB 5	1.00	Each
	31	027217020	Untreated Base Course (Plan Quantity)	3,002.00	cu yd
	32	027417050	HMA - 1/2 inch	20.00	Ton
	33	027437050	HMA - Bike/Ped Path 3/8 inch	2,495.00	Ton
	34	027487020	Emulsified Asphalt (Tack)	4.00	Ton
	35	027717059	Perpendicular/Parallel Pedestrian Access Ramp	6.00	Each
	36	02772700*	Tactile Directional Indicator	49.00	ft
	37	027767010	Concrete Sidewalk	3,810.00	sq ft
	38	027767025	Concrete Curb and Gutter Type B1	226.00	ft
	39	027767030	Concrete Flatwork, 4 inch thick	453.00	sq ft
	40	02776704P	Thickened Edge Sidewalk	322.00	sq ft
	41	027767050	Concrete Flatwork, 7 inch thick	1,017.00	sq ft
	42	02776705P	Decorative Concrete, 4 Inch Thick, Light Brown	2,837.00	sq ft
	43	02817700*	(2 Rail) Split Rail Fence	363.50	ft
	44	028217008	6 ft Chain Link Fence, Type I	1,434.00	ft
	45	02821700P	8 ft Chain Link Fence, Type I with Privacy Slats	426.60	ft
	46	028217072	Chain Link Gate, H= 4 ft X W= 10 ft	6.00	Each
	47	028217096	Chain Link Gate, H= 4 ft X W= 16 ft	2.00	Each
	48	028217100	Chain Link Gate, H= 6 ft X W= 16 ft	1.00	Each
	49	028227030	Right-of-Way Fence, Type D (Metal Post)	6,809.90	ft
	50	028227075	Right-of-Way Gate 8 ft	2.00	Each
	51	02826702*	Decorative Fence	55.00	ft
	52	029127030	Contractor Furnished Topsoil	2,724.00	sq yd
20 - STRUCTURES	Base				
	53	020567025	Granular Backfill Borrow (Plan Quantity)	30.00	cu yd
	54	02824702P	Ornamental Fence	226.30	ft
	55	02862710D	Modular Block Gravity Wall Est. Lump Qty: ___188___sq ft	1.00	Lump

Bid Items List Report

Base Bid Items					
Container	Description				
	Line No.	Item Number	Item Name	Quantity	Unit
20 - STRUCTURES	56	02862720D	Modular Block Gravity Wall Est. Lump Qty: ___876___sq ft	1.00	Lump
	57	02862730D	Modular Block Gravity Wall Est. Lump Qty: ___545___sq ft	1.00	Lump
	58	032117010	Reinforcing Steel - Coated (Plan Quantity)	3,145.00	Lb
	59	03310701D	Structural Concrete Est. Lump Qty: 30 cu yd	1.00	Lump
	60	051257010	Prefabricated Steel Truss Bridge	1.00	Lump
	61	058317010	Compression Joint Seal (Type A)	26.00	ft
	62	099817010	Concrete Coating (Plan Quantity)	406.00	sq ft
30 - LANDSCAPING	Base				
	63	02813700*	Restore Sprinkler System	1.00	Lump
	64	029117010	HECP Type 1 (Plan Quantity)	9,776.00	sq yd
	65	029127000	Strip and Stockpile Salvaged Topsoil (Plan Quantity)	900.00	sq yd
	66	029127010	Spread Salvaged Topsoil (Plan Quantity)	900.00	sq yd
	67	029227010	Drill Seed (Plan Quantity)	2,696.00	sq yd
	68	029227030	Broadcast Seed (Plan Quantity)	7,080.00	sq yd
	69	029227070	Turf Sod	28.00	sq yd
	70	02933701*	Landscaping Rock	2,162.00	sq ft
	71	02933702*	Remove, Stockpile, and Replace Landscaping Rock	10,000.00	sq ft
	72	02933703*	Remove and Replace Landscaping Curb	30.00	ft
40 - SIGNING	Base				
	73	027657050	Pavement Marking Paint	31.19	gal
	74	027657075	Pavement Marking Paint (Stop Line, Crosswalk-12 inch)	198.62	ft
	75	028917026	Sign Type A-1, 12 Inch X 24 Inch	3.00	Each
	76	02891702P	Sign Type A-1 18 inch x18 inch	5.00	Each
	77	028917030	Sign Type A-1, 21 inch X 15 inch	4.00	Each
	78	028917060	Sign Type A-1, 30 inch X 30 inch	5.00	Each
	79	028917065	Sign Type A-1, 36 inch X 36 inch	4.00	Each
	80	02891706P	Sign Type A-1, 14 inch X 6 inch	4.00	Each
	81	028917285	Relocate Sign Less Than 20 Square Feet	14.00	Each

Bid Items List Report

Base Bid Items						
Container	Description					
	Line No.	Item Number	Item Name		Quantity	Unit
40 - SIGNING	82	028917300	Small Sign Tubular Steel Post Base (B1)		14.00	Each
	83	028917320	Slipbase Sign Base (B3)		23.00	Each
	84	028917365	Sign Post P3		23.00	Each
180 - TIME AND/OR LANE RENTAL	Base					
	85	00221700*	Contract Time		Time Range: 60 - 130	Cal d
	86	00221701*	Contract Time		Time Range: 1 - 3	Cal d