Town of New Castle
Asphalt Milling and Overlay 2025
Bid Schedule
Addendum: E

Location/Description	Unit	Estimated Quantity	Unit Price	Extended Price
1. Aster Ct				
Edge Milling 1.75" Depth	LF	360		
Butt Milling (20'X9')	SF	180		
2"overlay (6,080 SF cul-de-sac)+(20'X60')	SF	7,280		
2. West 2nd St.				
Butt Milling (25'X9')	SF	225		
2"overlay (25'X132')	SF	3,300		
2. East 2nd St.				
Butt Milling (17'X9') X 3	SF	459		
2"overlay (17'X250')+(117'X17')	SF	6,239		
3. Mountain View Dr.				
Edge Milling 1.75 " depth	LF	1875		
Butt Milling (23'X9')	SF	207		
2"overlay (6,080 SF cul-de-sac)+(850'X38')	SF	38,380		
4. Safflower				
Edge Milling 1.75 " depth	LF	555		
Butt Milling (38'X9')	SF	342		
2"overlay (6,080 SF cul-de-sac)+(38'X160')	SF	12,160		

Location/Description	Unit	Estimated Quantity	Unit Price	Extended Price
5. Park Ave				
Grade and Prep	SF	5400		
Pave 3" (450'X12')	SF	5400		
Demo, Remove, & Dispose of existing Asphalt (112'X12')	SF	1344		
26 Tons of roadbase	Tons	26		
6. 7th St Alley				
Grade and Prep	SF	11000		
Pave 3" (1100'X10')	SF	11000		
75 Tons of roadbase	Tons	75		
7. Town Hall Parking Lot				
Grade and Prep	SF	2800		
Pave 3" (70'X40')	SF	2800		
39 tons of roadbase	Tons	39		
8. El Diente & South Wildhorse - Patch				
Saw Cut and Demo and dispose of Existing Asphalt	SF	676		
3" Patch (26'X26')	SF	676		
9. North Wildhorse & Castle Valley BLVD - Patch				
Saw Cut and Demo and dispose of Existing Asphalt	SF	390		
3" Patch (26'X15')	SF	390		
10. Stag Ct & Deer Valley - Patch				
Saw Cut and Demo and dispose of Existing Asphalt	SF	1,491		
3" Patch (36'X23')+(51'X13')	SF	1,491		
11. Skate Park to Pyramid Dr - Trail				
Demo and Dispose of Existing Asphalt	SF	16,603		
Pave 2" (1563'X9')+(317'X8')	SF	16,603		

Location/Description	Unit	Estimated Quantity	Unit Price	Extended Price
12. North Wildhorse - Trail				
Demo and Dispose of Existing Asphalt	SF	11,520		
Pave 2" (1440'X8')	SF	11,520		
13. Castle Valley BLVD & KSE Roundabout - Trail				
Demo and Dispose of Existing Asphalt	SF	3,030		
Pave 2" (303'X10')	SF	3,030		
11. Mobilization				
Total Mobilization	LS	1		
12. Traffic Control				
For all Locations	LS	1		
13. Man Hole and Valve Box Risers				
For all Locations	LS	1		

Please refer to New Castle Streets Maintenance Standards when bidding.

Edge Milling shall be 7' in width

Butt Joint milling shall be the width of the road and approximately 9' in length

Asphalt milling material will be disposed of on Town property free of charge.

5% Performance Bond Required. No Liquidated Damages

Total Price _____

Bidder Name/Company _____