

PRE-BID AGENDA

11:00 – WELCOME

11:00 – SIGN-IN

11:15 – INTRODUCTIONS; NAME, COMPANY, SPECIALITY

11:30 – SOLICITATION INFORMATION

- Submit all questions at time of site visit to the Contracting Officers Representative (COR)
Offeror's will be asked to confirm all verbal questions are submitted in writing to the Contracting Officer, Mr. Lucas Dahlman
- Questions due no later than Thursday, May 21st, 11:00 AM Central Time
- Quotes due no later than Wednesday, June 10th, 11:00 AM Central Time
- Evaluation and basis for award is in the solicitation. Ensure each factor is addressed in your proposal. Address biobased

11:35 – ADDITIONAL INFORMATION

General operating season = June through October

Period of Performance = 07/06/2026 to 10/15/2027

Stockpiled aggregates = 16,000 tons

State certified belt scale = 3

Sampling and testing = 15

UAV survey = 3

11:45 – SITE WALK

Additional questions and discussion

13:00 – END PRE-BID

Question and Answers

- **What is inspected for weeds? What is lead time for weed inspections?**
 - All heavy equipment. The only equipment that is not inspected prior to mobilization onto the project site is service vehicles.
 - Lead time for heavy equipment inspection is a minimum of five (5) working days to allow a representative from the Forest Service to inspect equipment.
- **Will the contractor be responsible for drone survey?**
 - Yes. The separate flights are estimated to take approximately 30 minutes each. There will be one flight prior to the commencement of gravel crushing operations, one flight during operations, and one final flight at the conclusion of gravel crushing operations. The flight information will be provided to the Contracting Officer. The drone pilot must be a Certified Remote Pilot per FAA Small UAS (Part 107).
- **Will the current stockpile be gone or segregated?**
 - To be determined. If the current stockpile is not removed prior to the commencement of operations, the new stockpile will be placed in a location as determined on the ground by the Contracting Officer.
- **Where can brush be stockpiled and can it be burned?**
 - Brush can be stockpiled adjacent to the excavation area either to the north – northwest, north, or north-northeast. At the conclusion of crushing operations, it will be scattered on the slopes of the excavated areas.
 - No burning of the brush will be allowed.
- **Where will topsoil be stockpiled?**
 - Topsoil will be stockpiled adjacent to the excavation area either to the north – northwest, north, or north-northeast. At the conclusion of crushing operations, it will be scattered on the slopes of the excavated areas.
- **Could live trees be cut? If so, can they be hauled off site?**
 - Yes. Live trees can be cut. Trees removed from the project area can be hauled off-site. A fuelwood permit must be purchased from the Forest Service to haul trees off-site.

- **If trees are left on site, how will they be disposed of?**
 - If trees are left on-site, they will be limbed and cut to lengths of four (4) feet or less and decked in an area as identified on the ground by the Contracting Officer.
- **Will camping be permitted on site?**
 - Yes. Camping on-site will be permitted. A camping permit will be provided by the Contracting Officer to the contractor for a predetermined length of time as agreed upon prior to mobilization onto the site.